

ENGINEERING DEPARTMENT

	STANDARD OPERATING PROCE	Revision No. Supersedes No.	
Department: Engineering			
TITLE: De-Scaling of Mu	lticolumn Distillation Plant		
SOP No.	Revisi	on No.	
Effective Date	Supers	sedes No.	
Review Date	Page N	No. 1 of 5	

1.0 **OBJECTIVE:**

The purpose of this SOP is:

1.1 The Objective of this SOP is to describe the procedure for De-scaling of Multi Column Distillation Plant (MCDP).

2.0 **SCOPE:**

2.1	This SOP is applicable for the procedure for De-scaling of Multi Column Distillation Plant.
	at

RESPONSIBILITY: 3.0

- 3.1 The Maintenance Operator shall be responsible:
 - 3.1.1 Responsible for De scaling of MCDP.
 - Responsible for maintaining the De scaling record. 3.1.2
- 3.2 The Maintenance Engineer shall be responsible:
 - 3.2.1 Responsible for assurance for proper De scaling of the plant.
 - 3.2.2 Responsible to take corrective action if any deviation.

ACCOUNTABILITY 4.0

Head -Engineering Services

5.0 **PROCEDURE:**

5.1 DE-SCALING OF COLUMN:

5.1.1 Before starting the process switch OFF the main control panel of MCDP.



ENGINEERING DEPARTMENT

STANDARD OPERATING PROCEDURE

Department: Engineering

TITLE: De-Scaling of Multicolumn Distillation Plant

SOP No.	Revision No.	
Effective Date	Supersedes No.	
Review Date	Page No.	2 of 5

- 5.1.2 Connect the feed water pump suction and out let of the last column to chemical preparation Stainless Steel (SS) tank.
- 5.1.3 Prepare 6 kg sodium hydroxide flakes and 200 liter purified water in chemical tank. Mix the solution properly.
- 5.1.4 Re-circulate the solution through the columns for 2 hrs by switch ON the feed water pump.
- 5.1.5 After 2 hours switch 'Off' the pump. Drain the solution and flush the column with purified water for neutralizing the system. (Check the pH, it should be7-8).
- 5.1.6 After neutralization of column, prepare 30 kg citric acid and 200 liter purified water in chemical tank and mixes the solution properly.
- 5.1.7 Re-circulate the solution through the columns for 1hr by switch 'On' the feed water pump.
- 5.1.8 After one hour, mix 9 kg Ammonic Bifloride into the citric acid solution and continue the re-circulation for another 2 hours.
- 5.1.9 After the 2 hour re circulation, mix 60 liters of Ammonia solution (commercial grade) and 1 liter Teapot into the citric acid Ammonic Bifloride solution. Continue the re circulation for 2 hours.
- 5.1.10 After 2 hours re circulation again mix 1.5 kg of Sodium Nitrite into the above solution and re circulate for another one hour.
- 5.1.11 Switch 'Off' the feed pumps and drains the solution from the columns.
- 5.1.12 Flush the columns with purified water for 5-6 hours.
- 5.1.13 After flushing the columns, check the pH and conductivity. It should be same as feed water. Otherwise continue the flushing till get the pH and conductivity.
- 5.1.14 Reconnect the feed pump suction line and outlet line of the last column.



ENGINEERING DEPARTMENT

STANDARD OPERATING PROCEDURE

Department: Engineering

TITLE: De-Scaling of Multicolumn Distillation Plant

SOP No.	Revision No.	
Effective Date	Supersedes No) .
Review Date	Page No.	3 of 5

5.2 DESCALING OF TOP COOLER (CONDENSOR):

- 5.2.1 Connect the cooling water pump suction and out let of the top cooler to chemical preparation SS tank.
- 5.2.2 Prepare 5 kg sulphamic acid (commercial grade) and 200-liter warm purified water in chemical tank. Mix the solution properly.
- 5.2.3 Re-circulate the solution through the top cooler for 2 hrs by switch ON the cooling water pump.
- 5.2.4 After 2 hours switch 'Off' the pump. Drain the solution and flush the top cooler with purified water for 4-5 hours.
- 5.2.5 After flushing check the pH and conductivity of the water. It should be same as feed purified water. Otherwise continue the flushing till get pH and conductivity.
- 5.2.6 Reconnect the feed pump suction line and outlet line of the top cooler.
- 5.2.7 Start the plant as per Ref. SOP.

5.3 FREQUENCY OF DESCALING:

5.3.1 De scaling of the columns and top cooler has to be carried out once in every year. (Frequency is decided on the basis of manufacture's recommendation).

6.0 ANNEXURES:

Annexure –I : Multi Column Distillation Plant De Scaling Record.

7.0 References (S)

Nil



ENGINEERING DEPARTMENT

STANDARD OPERATING PROCEDURE

Department: Engineering

TITLE: De-Scaling of Multicolumn Distillation Plant

SOP No.	Revision No.	
Effective Date	Supersedes No.	
Review Date	Page No.	4 of 5

8.0 Glossary

SOP : Standard Operating procedure

No : Number

MCDP : Multi Column Distillation Plant



ENGINEERING DEPARTMENT

STANDARD OPERATING PROCEDURE

Department: Engineering

TITLE: De-Scaling of Multicolumn Distillation Plant

SOP No.	Revi	vision No.			
Effective Date	Supe	ersedes No.			
Review Date	Page	ge No.	5 of 5		

ANNEXURE-I

MULTI COLUMN DISTILLATION PLANT (WFI) DE- SCALING RECORD

S.No.	De scaling done on	De scaling	De scaling	Time (hrs)	Remarks	Operator's Sign.	Engineer's Sign.
5.110.	De scannig done on	Next due on	From	To	Remarks	Sign.	Engineer's Sign.