

PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION	
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 1 of 11

USER REQUIREMENT SPECIFICATION

NAME OF THE ITEM: BOTTLE FILLING MACHINE

FUNCTIONAL AREA: PRODUCTION

PROTOCOL No. :



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION	
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 2 of 11

CONTENT

S.No.	<u>Description</u>
1.0	URS Approval
2.0	Objective
3.0	Responsibilities
4.0	Equipment Description & Identification
5.0	User Requirements
6.0	Complementary aspects
7.0	Safety and environmental Protection
8.0	Cleaning maintenance and service
9.0	Rules and Regulation
10.0	Scope of Delivery
11.0	Installation ,Commissioning and Tests
12.0	Qualification/Validation
13.0	Guarantee/Warrantee



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION		
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No	
FUNCTIONAL AREA: PRODUCTION	Page No.: 3 of 11	

1.0 URS APPROVAL:

Protocol Prepared By:

Functional area	Name	Signature	Date
Production			

URS Reviewed By:

Functional area	Name	Signature	Date
Production			
Quality Assurance			
Engineering			

URS Approved By:

Functional area	Name	Signature	Date
Head Engineering			
Head Manufacturing			
Head Quality			



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION	
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 4 of 11

2.0 Objective:

The purpose of this document is to ensure that all the critical aspects of the Equipment, cGMP & Safety features have been considered in designing the equipment/instrument and is properly documented.

3.0 Responsibilities:

In accordance with the document, following functions shall be responsible for initiation and finalization of Equipment user requirement specification. When the work is carried by contract/ consulting staff, all the work is to be performed under the oversight of

3.1 Preparation of Document

- User department to prepare the URS
- Ensures that the document is in compliance with current policies and procedures of cGMP regulations.
- Ensures that the content is sufficient, clearly defined, technically sound and accurate.
- It is a Guidance document to prepare the URS.

3.2 Review of Document

• To be reviewed by Head of the user department and functional department (Engineering & Quality assurance)

3.3 Approval of Document

• Approval of document by Head Manufacturing/Head Engineering/Head Quality.

4.0 Equipment Description & Identification:

4.1 Scope:

This document covers all aspects of Users requirements for the Equipment along with all Attachment, Spare Parts, Change Parts and Accessories to be used in

Scope incorporates understanding and documentation of critical requirements such as system requirements, cGMP requirements, safety requirements, documentation requirements and operational requirements.

4.2 Purpose:

Purpose of equipment is used in production area for the capping of the bottles.



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION	
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 5 of 11

5.0 USER REQUIREMENTS

5.1 System Requirements:

S.No.	SYSTEM COMPONENTS	SYSTEM REQUIREMENTS	
01.	Identification	Details of Make, Name, Serial. No., Capacity, Model and Year of	
	(In case of Equipment /Instrument)	manufacture should be available	
02.	Model/Type	As per cGMP requirements.	
03.	Capacity	240 bottle/min	
04.	Potential Suppliers	1. JP machines.	
		2. Anchor Mark	
05.	Contact parts	SS304 with Mat finish	
06.	Non contact parts	SS304 with matt finish	
07.	Non metallic contact parts	Any material with food grade quality having no	
		Potential impact on the products.	
		2. Durable.	
		3. Must be easily cleanable.	
08.	Motor & Electrical installations	As per machine requirement	
09.	Machine assemblies	Must be covered with SS 304 with matt finish.	
10.	Machine adjustments	Setting with zero clearance with good accuracy.	
11.	Packaging & Transport	Should be packed and transported in such a way to avoid any	
		damage during transportation.	
12.	No. of requirements	01	
13.	Requirements for any power failure backup's	To be backed up by installed in-house DG set.	



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION	
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 6 of 11

5.2 Technical Description

S.No.		Specification	SYSTEM REQUIREMENTS
1	Specification:		YES
	Production Rate	e: up to 240 bottle/min.	
	Bottle Diameter	r: 30-80 mm	
	Bottle Height	:55 -150mm	
	Cap Diameter	:20-45mm	
	Cap Height	:14-20mm	
	Main Motor	:2.0 HP with VFD.	
	Conveyor	:0.5HP with VFD	
	Orienter	:0.25HP	
	Height adjuster	:0.5HP	
2.	Emergency off	switch	YES

6.0 COMPLEMENTARY ASPECTS

6.1 Training

S.No.	Specification	SYSTEM REQUIREMENTS
6.1.1	The vendor Shall supply all available information for the adequate	YES
	exploitation of equipment. For the Compliance of this purpose at the Job	
	site and/ or at the Vendors Shop. Vendor's technical staff shall train	
	customer's personnel. The scope of the	
	Training will be agreed during the contract signature.	
6.1.2	The supplier is to include the personnel training activities. The supplier is	YES
	to specify the foreseen time for:	
	Operator/Supervisor training	
	Manager Training	
	Electrical maintenance training	
	Mechanical Maintenance training	
6.1.3	The supplier is to specify the personnel background needed for each of the	YES
	operators maintenance.	

6.2 Pre Delivery Qualifications (FAT)

S.No.	Specification	SYSTEM REQUIREMENTS
6.2.1	The System or its parts as provided for in the scope of supply shall be pre-	YES
	installed at the vendors shop prior to delivery to customer site. Installation	
	will be completed and documented including mechanical parts as well as	
	electrical connections of all parts to facilitate taking over tests at Vendors	
	shop prior to delivery.	
	FAT protocol must be send by supplier to company prior to FAT for	
	approval. FAT protocol should have provision of trial.	



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION		
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No	
FUNCTIONAL AREA: PRODUCTION	Page No.: 7 of 11	

6.3 Supplier Technical Documentation Requirements:

S.No.	COMPONENTS	REQUIREMENTS
6.3.1 Draw	vings	Pre Installation Requirements will be supplied by Vendor
•	Equipment/Systems electrical drawing. Point to point wiring diagram	
6.3.2 LIST	Equipment and instrument list with Component description. Electrical component parts list with Description. Function check list. Documentation list.	YES YES YES YES List of spares required for smooth operation will be provided by the Vendor at the time of ordering.

6.4 Technical Manuals

S.No.	Specification	Requirements
6.4.1	Operating handbook	YES
6.4.2	Trouble Shooting Guide	YES
6.4.3	Equipment Description	YES
6.4.4	Equipment specification	YES
6.4.5	Maintenance Handbook	YES

7.0 SAFETY AND ENVIRONMENTAL PROTECTION

S.No.	Specification	Requirements
7.1	All motors have to be thermally Protected.	YES
7.2	All the Installation must be in accordance with the cGMP.	YES
7.3	The cGMP concerning safety must be applied.	YES

8.0 CLEANING MAINTENANCE AND SERVICE

S.No.	Specification
8.1	In accordance with cGMP guidelines the units must be easy to clean, to disinfect, and where necessary.
8.2	The Supplier should guarantee that, if required, a service team can be on site within one working day.
8.3	The design should be such as to allow mechanical cleaning of the surface and that the cleanliness of the surface can be checked easily.
8.4	All machine parts, in particular instrumentation, should be constructed so that they can be easily removed and calibrated.
8.5	All special tools required for running and maintenance should be best.
8.6	A spare parts delivery guarantee with in time.



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION		
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No	
FUNCTIONAL AREA: PRODUCTION	Page No.: 8 of 11	

9.0 RULES AND REGULATION

These standards, recommendation and requirements are considered the minimum. Specifications that are more stringent or expansive take the precedence. In case of conflict between published requirements, final determination is the responsibility of the Owners Representative.

10.0 SCOPE OF DELIVERY

S. No.	Specification	Requirements
10.1	Units described in the specific system requirements including all necessary controls and instrumentation.	YES
10.2	The complete mechanical and electrical installation.	YES
10.3	The Connections to all the necessary utilities, exhaust, and waste lines necessary for its operation.	Yes
10.4	All piping and cabling of the units itself.	YES
10.5	Wiring and cable run: all wiring and cable run is part of the supply will supply the main power switches to be located in correspondence to the electrical and control cabinets delivered by the equipment supplier.	YES
10.6	All internal contacts of the supplied equipment for the required utilities.	YES
10.7	Unload on site of the equipment: the supplier is required to define all the necessary handling devices required to the unloading operation. The supplier will inform at least 4 weeks in advance the day of delivery and the list of required handling devices.	YES
10.8	Assembling operation: the required consumable, the internal transportation, the assembling tools and the required personal are part of the supply.	YES
10.9	A complete set of commissioning spare parts.	YES
10.10	All special tools necessary for use and maintenance of the supplied equipment.	YES
10.11	A complete set of two years spare parts should be listed quoted and offered as option.	YES
10.12	All test activities as specified in this document.	YES
10.13	Training in the use and maintenance of the equipment.	YES
10.14	A complete set of documentation as specified In this document.	YES

11.0 INSTALLATION, COMMISSIONING AND TESTS

11.1 General

S.No.	Specification	Requirements
11.1.1	The Supplier must specify for each piece of equipment the Guaranteed performance and the guaranteed system performance. These values will be tested during the acceptance tests.	YES
11.1.2	In addition the functionality described in the user requirements and detailed in the system specifications will be tested.	YES



PRODUCTION DEPARTMENT

NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 9 of 11

11.2 INSTALLATION, COMMISSION

Specification	Requirements
The commissioning tests will be carried out in accordance with a written test	YES
plan developed by the supplier with clearly stated test procedures and acceptance	
criteria.	
The supplier will approve successfully completed tests and will specify items	YES
requiring additional work. Representatives from Will attend and	
participate in the commissioning tests as required.	
The installation and commissioning of the system will be performed at the	YES
Facility by the supplier.	
The commissioning can only start once all the foreseen documents have been	YES
delivered by the supplier to	
All equipment should be properly installed, adjusted, leveled, tagged, and	YES
connected with utilities.	
Point to point checks on wiring and pneumatic should be performed.	YES
All instruments should be properly calibrated.	YES
A equipment (instrument) used for qualification must be listed and approved by	YES
The calibration equipment must have all the necessary documents to	YES
demonstrate their maintenance & use.	
All this equipment must be calibrated periodically and evidenced by certificate.	YES
Verification that the interior surfaces of equipment are free of practices and dirt	YES
and all points of product contact meet the specified material requirements.	
All the clearances and tolerances specified in the drawing or recommended by	YES
component manufacturers are correct.	
On site verification that valves and other equipment with moving parts are in	YES
their normal position if in a power down condition and move in the correct	
direction with the correct speed and precision.	
Verification that all the Input and Output points are connected and labeled	
according to the documentation and that all the along the input values have been	
scaled in accordance with the system specification and process requirements.	
That all equipment components requiring configuration	
The commissioning should demonstrate that the system supplied by the supplier	YES
has been properly installed and that the functions are in accordance with	
User Requirements specifications, Vendors System specifications	
	The commissioning tests will be carried out in accordance with a written test plan developed by the supplier with clearly stated test procedures and acceptance criteria. The supplier will approve successfully completed tests and will specify items requiring additional work. Representatives from



PRODUCTION DEPARTMENT

USER I	REQUIREN	MENT SPE	CIFICATION
---------------	----------	----------	------------

NAME OF ITEM: Bottle Filling Machine	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 10 of 11

Manuals and other Documentation.	

11.3 Site Acceptance Test (SAT)

S.No.	Specification	Requirements
11.3.1	This test will be carried out once the commissioning will be completed. The scope will be to verify the performance and the functionality of the system integrated with the other factory systems.	YES
11.3.2	The test will be carried out to verify the system response with the expected productivity of the system.	YES
11.3.3	Details on the test realization will be defined during the project Phase. The supplier is asked to specify the proposed duration for SAT and the standard procedure proposed.	YES
11.3.4	During SAT the required functionality, performances and system reliability are met.	YES
11.3.5	The Functionality described in the User Requirements Specification and in the System Specifications are verified and met.	YES
113.6	All the documentation agreed has been delivered.	YES

12.0 QUALIFICATION/VALIDATION

S.No.	Specification	Requirements
12.1	The maintenance Qualification is responsibility of the customer. However, the supplier is responsible for delivering the basic documents for maintenance qualification.	YES
12.2	This includes all side costs such as: calibration measuring equipment and instruments: manpower (IQ and OQ will take place completely on)	YES
12.3	Time Schedule for IQ/OQ execution will be developed by	YES
12.4	Suppliers personnel used for IQ/OQ must be well trained and experienced. This should be documented.	YES
12.5	The onsite test run performed by the supplier might become part of the IQ.	YES
12.6	Main IQ/OQ steps such as calibration must be performed and documented in accordance to a SOP approved by	YES
12.7	All equipment used for qualification must be listed and approved by	YES
12.8	The last Recalibration of all this equipment should be less than 06 month old. Proofed by Certificate.	YES
12.9	OQ can only start after IQ approved by	YES
12.10	IQ will be carried out by	YES
12.11	Part of the OQ will be carried out by During commissioning and SAT phase. OQ will include the tests performed by the supplier.	YES
12.12	After installation of the equipment at customers site. Complementary IQ & OQ tests will be performed by the Customer and may be supervised by a member of Technical staff.	YES
12.13	Qualification documents	DQ, IQ, OQ, MOC and Test



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION		
NAME OF ITEM: Bottle Filling Machine	PROTOCOL No	
FUNCTIONAL AREA: PRODUCTION	Page No.: 11 of 11	

	Certificate.

13.0 GAURANTEE/WARRANTEE

S.No.	Specification	Requirements
14.1	The System must be guaranteed including all the sub- system and components for a period of 12 months from the date of the system acceptance for a 03- shift operation.	YES
14.2	The servicing companies involved for the Sub- systems maintenance must be declared and the maintenance group organization described. Furthermore, the supplier will be directly responsible of the system assistance and the required operation will be co- ordinate by him.	YES
14.3	In case of failures, the intervention will be guaranteed by the supplier within a maximum time limit. The supplier is asked to specify the maximum time limit.	YES
14.4	The supplier is asked to propose as option maintenance and assistance contract after the guarantee expiration.	YES