

. PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 1 of 11

USER REQUIREMENT SPECIFICATION

NAME OF THE ITEM: STATIC PASS BOX

FUNCTIONAL AREA: PRODUCTION

PROTOCOL No. :



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 2 of 11

CONTENT

Sr. No.	Description
1.0	URS Approval
2.0	Objective
3.0	Responsibilities
4.0	Equipment Description & Identification
5.0	User Requirements
6.0	Complementary aspects
7.0	Safety and environmental Protection
8.0	Cleaning maintenance and service
9.0	Rules and Regulation
10.0	Scope of Delivery
11.0	Installation ,Commissioning and Tests
12.0	Qualification/Validation
13.0	Guarantee/Warrantee



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 3 of 11

1.0 URS APPROVAL:

Protocol Prepared By:

Functional area	Name	Signature	Date
Production			

URS Reviewed By:

Functional area	Name	Signature	Date
Production			
Engineering			
Quality assurance			

URS Approved By:

Functional area	Name	Signature	Date
Head Engineering			
Head Manufacturing			
Head Quality			



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 4 of 11

2.0 Objective:

The purpose of this document is to ensure that all the critical aspects of the Equipment, cGMP & Safety features have been considered in designing the equipment/instrument and is properly documented.

3.0 Responsibilities:

In accordance with the document, following functions shall be responsible for initiation and finalization of Equipment user requirement specification. When the work is carried by contract/ consulting staff, all the work is to be performed under the oversight of

3.1 Preparation of Document

- User department to prepare the URS
- Ensures that the document is in compliance with current policies and procedures of cGMP regulations.
- Ensures that the content is sufficient, clearly defined, technically sound and accurate.
- It is a Guidance document to prepare the URS.

3.2 Review of Document

• To be reviewed by Head of the user department and functional department (Engineering & Quality assurance)

3.3 Approval of Document

• Approval of document by Head Manufacturing/Head Engineering/Head Quality.

4.0 Equipment Description & Identification:

4.1 Scope:

This document covers all aspects of Users requirements for the Equipment along with all Attachment, Spare Parts, Change Parts and Accessories to be used in

Scope incorporates understanding and documentation of critical requirements such as system requirements, cGMP requirements, safety requirements, documentation requirements and operational requirements.

4.2 Purpose:

To prevent the contamination and the transfer of material from non critical to non critical area



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 5 of 11

5.0 USER REQUIREMENTS

5.1 System Requirements:

Sr. No.	SYSTEM COMPONENTS	SYSTEM REQUIREMENTS
1.	Identification (In case of Equipment	Details of Make, Name, Serial. No., Capacity, Model and Year of
	/Instrument)	manufacture should be available
2.	Model/Type	Static pass box
3.	Dimension	600 x 600 x 600 mm
4.	Potential Suppliers	GMP or equivalent supplier
5.	Contact parts	SS304 with Mirror finish
6.	Non contact parts	SS304 with matt finish
7.	Non metallic contact parts	Any material with food grade quality having no Potential impact on the products.Durable.Must be easily cleanable.
8.	Packaging & Transport	Should be packed and transported in such a way to avoid any damage during transportation.
9.	No. of requirements	08
10.	Requirements for any power failure backup's	To be backed up by installed in-house DG set.

5.2 Technical Description

Sr. No.	Specification	SYSTEM REQUIREMENTS
1.	Door interlocking system	YES
2.	Door handle	YES
3.	Toughened glass view	YES
4	Machine mounting	Machine is to be mounted on the floor between two area should be installed firmly to resist any vibration during operation.
5	UV Light	Yes





PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 6 of 11

6.0 COMPLEMENTARY ASPECTS

6.1 Training

Sr. No.	Specification	SYSTEM REQUIREMENTS
6.1.1	The vendor Shall supply all available information for the	YES
	adequate exploitation of equipment. For the Compliance of	
	this purpose at the Job site and/ or at the Vendors Shop.	
	Vendor's technical staff shall train customer's personnel. The	
	scope of the	
	Training will be agreed during the contract signature.	
6.1.2	The supplier is to include the personnel training activities.	YES
	The supplier is to specify the foreseen time for:	
	Operator/Supervisor training	
	Manager Training	
	Electrical maintenance training	
	Mechanical Maintenance training	
6.1.3	The supplier is to specify the personnel background needed	YES
	for each of the operators maintenance.	

6.2 Pre Delivery Qualifications (FAT)

Sr. No.	Specification	SYSTEM REQUIREMENTS
6.2.1	The System or its parts as provided for in the scope of supply shall be pre-installed at the vendors shop prior to delivery to customer site. Installation will be completed and documented including mechanical parts as well as electrical connections of all parts to facilitate taking over tests at Vendors shop prior to delivery.	NA

6.3 Supplier Technical Documentation Requirements:

Sr. No.	COMPONENTS	REQUIREMENTS
6.3.1	Drawings	Pre Installation Requirements will be supplied
	• Equipment/Systems electrical drawing.	by Vendor
	Point to point wiring diagram	
6.3.2	LIST.	
	• Equipment and instrument list with Component description.	YES
	• Electrical component parts list with Description.	YES
	• Function check list.	YES
	• Documentation list.	YES





PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 7 of 11

6.4 Technical Manuals

Sr. No.	Specification	Requirements
6.4.1	Operating handbook	YES
6.4.2	Trouble Shooting Guide	YES
6.4.3	Equipment Description	YES
6.4.4	Equipment specification	YES
6.4.5	Maintenance Instruction	YES

7.0 SAFETY AND ENVIRONMENTAL PROTECTION

ſ	Sr. No.	Specification	Requirements
Ī	7.1	All the Installation must be in accordance with the cGMP.	YES
	7.2	The cGMP concerning safety must be applied.	YES

8.0 CLEANING MAINTENANCE AND SERVICE

Sr. No. Specification	
8.1	In accordance with cGMP guidelines the units must be easy to clean, to disinfect, and where necessary.
8.2	The Supplier should guarantee that, if required, a service team can be on site within one working day.
8.3	The design should be such as to allow mechanical cleaning of the surface and that the cleanliness of the surface can be checked easily.
8.4	All machine parts, in particular instrumentation, should be constructed so that they can be easily removed.
8.5	All special tools required for running and maintenance should be best.
8.6	A spare parts delivery guarantee with in time.

9.0 RULES AND REGULATION

These standards, recommendation and requirements are considered the minimum. Specifications that are more stringent or expansive take the precedence. In case of conflict between published requirements, final determination is the responsibility of the Owners Representative.



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 8 of 11

10. SCOPE OF DELIVERY

Sr. No.	Specification	Requirements
10.1	Units described in the specific system requirements including all necessary	YES
	controls and instrumentation.	
10.2	The complete mechanical and electrical installation.	YES
10.3	The Connections to all the necessary utilities necessary for its operation.	YES
10.4	All piping and cabling of the units it.	YES
10.5	Wiring and cable run: all wiring and cable run is part of the supply. will supply the main power switches to be located in correspondence to the electrical and control cabinets delivered by the equipment supplier.	YES
10.6	All internal contacts of the supplied equipment for the required utilities.	YES
10.7	Unload on site of the equipment: the supplier is required to define all the necessary handling devices required to the unloading operation. The supplier will inform at least 4 weeks in advance the day of delivery and the list of required handling devices.	YES
10.8	Assembling operation: the required consumable, the internal transportation, the assembling tools and the required personal are part of the supply.	YES
10.9	A complete set of commissioning spare parts.	YES
10.10	All special tools necessary for use and maintenance of the supplied equipment.	YES
10.11	A complete set of two years spare parts should be listed quoted and offered as option.	YES
10.12	All test activities as specified in this document.	YES
10.13	Training in the use and maintenance of the equipment.	YES
10.14	A complete set of documentation as specified in this document.	YES





PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION

NAME OF ITEM: STATIC PASS BOX	PROTOCOL No
FUNCTIONAL AREA: PRODUCTION	Page No.: 9 of 11

11.0 INSTALLATION, COMMISSIONING AND TESTS

11.1 General

Sr. No.	Specification	Requirements
11.1.1	The Supplier must specify for each piece of equipment the Guaranteed performance and the guaranteed system performance. These values will be tested during the acceptance tests.	YES
11.1.2	In addition the functionality described in the user requirements and detailed in the system specifications will be tested.	YES

11.2 INSTALLATION, COMMISSION

Sr. No.	Specification	Requirements
11.2.1	The commissioning tests will be carried out in accordance with a written test plan	YES
	developed by the supplier with clearly stated test procedures and acceptance	
	criteria.	
11.2.2	The supplier will approve successfully completed tests and will specify items	YES
	requiring additional work. Representatives from Will attend and	
	participate in the commissioning tests as required.	
11.2.3	The installation and commissioning of the system will be performed at the	YES
	Facility by the supplier.	
11.2.4	The commissioning can only start once all the foreseen documents have been	YES
	delivered by the supplier to	
11.2.5	All equipment should be properly installed, adjusted, leveled, tagged, and	YES
	connected with utilities.	
11.2.6	Point to point checks on wiring and pneumatic should be performed.	YES
11.2.7	A equipment (instrument) used for qualification must be listed and approved by	YES
11.2.8	Verification that the interior surfaces of equipment are free of practices and dirt and	YES
	all points of product contact meet the specified material requirements.	
11.2.9	All the clearances and tolerances specified in the drawing or recommended by	YES
	component manufacturers are correct.	
11.2.10	Verification that all the Input and Output points are connected and labeled	YES
	according to the documentation and that all the along the input values have been	
	scaled in accordance with the system specification and process requirements. That	
	all equipment components requiring configuration.	



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION				
NAME O	NAME OF ITEM: STATIC PASS BOX PRO		TOCOL No	
FUNCTIO	FUNCTIONAL AREA: PRODUCTIONPage		No.: 10 of 11	
Sr. No.	Specification		Requirements	
11.2.11	The commissioning should demonstrate that the system supplied by the supplicit by the supplied by the supplicit by the supplis	•••••	YES	

11.3 Site Acceptance Test (SAT)

Sr. No.	Specification	Requirements
11.3.1	This test will be carried out once the commissioning will be completed. The scope	YES
	will be to verify the performance and the functionality of the system integrated	
	with the other factory systems.	
11.3.2	The test will be carried out to verify the system response with the expected	YES
	productivity of the system.	
11.3.3	Details on the test realization will be defined during the project Phase. The supplier	YES
	is asked to specify the proposed duration for SAT and the standard procedure	
	proposed.	
11.3.4	During SAT the required functionality, performances and system reliability are	YES
	met.	
11.3.5	The Functionality described in the User Requirements Specification and in the	YES
	System Specifications are verified and met.	
113.6	All the documentation agreed has been delivered.	YES

12.0 QUALIFICATION / VALIDATION

Sr. No.	Specification	Requirements
12.1	The maintenance Qualification is responsibility of the customer. However, the supplier is responsible for delivering the basic documents for maintenance qualification.	YES
12.2	Time Schedule for IQ/OQ execution will be developed bywith the supplier.	YES
12.3	Suppliers personnel used for IQ/OQ must be well trained and experienced. This should be documented.	YES
12.4	The onsite test run performed by the supplier might become part of the IQ.	YES
12.9	OQ can only start after IQ approved by	YES
12.5	IQ will be carried out by During Installation phase. IQ will include the tests performed by the supplier.	YES
12.6	Part of the OQ will be carried out by During commissioning and SAT phase. OQ will include the tests performed by the supplier.	YES
12.7	After installation of the equipment at customers site. Complementary IQ & OQ tests will be performed by the Customer and may be supervised by a member of Technical staff.	YES



PRODUCTION DEPARTMENT

USER REQUIREMENT SPECIFICATION					
NAME OF ITEM: STATIC PASS BOX PRO'			OCOL No		
FUNCTIONAL AREA: PRODUCTIONPage 1		No.: 11 of 11			
Sr. No.	Specification		Requirements		

13.0 GAURANTEE/WARRANTEE

Sr. No.	Specification	Requirements
13.1	The System must be guaranteed including all the sub- system and components for a period of 12 months from the date of the system acceptance for a 03- shift operation.	YES
13.2	The servicing companies involved for the Sub- systems maintenance must be declared and the maintenance group organization described. Furthermore, the supplier will be directly responsible of the system assistance and the required operation will be co-ordinate by him.	YES
13.3	In case of failures, the intervention will be guaranteed by the supplier within a maximum time limit. The supplier is asked to specify the maximum time limit.	YES
13.4	The supplier is asked to propose as option maintenance and assistance contract after the guarantee expiration.	YES