



**PHARMA DEVILS**

PRODUCTION DEPARTMENT

**USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER**

# **USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER**



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Prepared by       |           |      |
|-------------------|-----------|------|
| Name/ Designation | Signature | Date |
|                   |           |      |

| Checked by        |           |      |
|-------------------|-----------|------|
| Name/ Designation | Signature | Date |
|                   |           |      |
|                   |           |      |
|                   |           |      |
|                   |           |      |

| Approved by       |           |      |
|-------------------|-----------|------|
| Name/ Designation | Signature | Date |
|                   |           |      |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

### OVERVIEW:

#### EQUIPMENT DESCRIPTION

The Lyophilizer shall be used to freeze-dry the sterile aqueous solution of the product filled in half-stoppered glass vials or trays. Lyophilizer shall stopper the vial before unloading.

The lyophilizer shall be integrated with semi-automatic loading and unloading system to load and unload the vials in and from lyophilizer respectively.

The lyophiliser shall have facility to directly fill the trays with the product solution

The lyophilizer shall be configured as per the equipment location layout the lyophilizer (the equipment layout is attached as Annex 1)

As the product to be dried is sterile, the loading side shall be covered by Laminar air flow system.

This URS is to be complied by the vendor who will be responsible for design, fabrication, installation at site and qualification of Lyophilizer and loading/unloading system.

#### REFERENCE STANDARD/GUIDELINE FOR EQUIPMENT

The equipment should comply with the following guidelines/standard:

##### GMP-Regulations

- Regulation for implementation of the drug administration law of the People's Republic of China EU-GMP-Guideline Part 1, Annexes 1, 15 & 17
- Code of Federal Regulations (CFR) 21, Part 210: cGMP in Manufacturing, Processing, Packing and Holding of Drugs; General
- 21 CFR Part 211: Current Good Manufacturing Practice for finished Pharmaceuticals
- 21 CFR Part 11: Electronic Records; Electronic Signatures

##### FDA Guidance for Industry

- Sterile Drug Products Produced by Aseptic Processing
- Documentation for Sterilisation Process Validation

##### GAMP

- The Good Automated Manufacturing Practice (GAMP) Guide for Validation of Automated Systems in Pharmaceutical Manufacture, Vol. 5



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

Vendor shall provide response as Yes or No against each specification for the compliance of their offered equipment in the remarks column and send the copy along with the quotation.

| Specifications  | Compliance   |
|---|--|
| <b>3.0 Process Description</b>  |  |
| <b>3.1 Input &amp; Charging method</b>  |  |
| 3.1.1 <b>Input:</b> Aqueous solution of the product filled in half stoppered glass vials or intrays. Vial sizes are <b>ISO 2R, 6R, 10R according to DIN-ISO 8362-1 and 8362-4.</b><br>For lyophilization fill volume could be considered as 50% of the total fill capacity of the vial.   | Information  |
| 3.1.2 Freezing temperature of product: -55°C  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.1.3 Maximum temperature during secondary drying: +70°C  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.1.4 Condenser temperature minimum : -75°C   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.1.5 600 kg ice condensing capacity  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.1.6 Vendor shall propose a cost effective design of the semi-automatic loading system, which should collect the vials from the upstream filling and stoppering system, and load the vials into lyophilizer without or little human intervention maintaining the sterility of the product.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.1.7 Loading system should consider the upstream filling capacity of 200 vials per minute (based on vial size 10R).  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.1.8 Loading shall be done at room temperature in closed manner within class A under unidirectional air flow.  | Information  |
| <b>3.2 Brief Process Steps</b>  |  |
| 3.2.1 The lyophilization shall have the following process steps <ul style="list-style-type: none"> <li>• Vial lyophilisation               <ul style="list-style-type: none"> <li><input type="checkbox"/> Collection of filled and half stoppered vials from upstream filling &amp; stoppering machine</li> <li><input type="checkbox"/> Semi - automatic loading of vials in lyophilizer</li> <li><input type="checkbox"/> Lyophilization</li> <li><input type="checkbox"/> Pressing of stopper</li> <li><input type="checkbox"/> Semi-Automatic unloading of vials from lyophilizer</li> <li><input type="checkbox"/> Transfer of vials on to crimping machine</li> </ul> </li> <li>• Bulk Lyophilisation</li> </ul> | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications  | Compliance   |
|---|--|
| <input type="checkbox"/> Filling of sterile bulk in tray<br><input type="checkbox"/> Lyophilisation<br><input type="checkbox"/> Filling in containers ( 4kg or 8 kg)  |  |
| <b>3.3 Output &amp; Discharging method</b>  |  |
| 3.3.1 <b>Output:</b> sterile powder of the product.<br>Vendor shall propose a cost effective design options of the semi-automatic unloading system which should collect the vials from the lyophilizer and discharge the vials on the conveying system of the down stream crimping machine. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 3.3.2 Unloading shall be done at room temperature in closed manner within class A Isolator under unidirectional air flow.   | Information  |
| <b>4.0 Productivity Requirement</b>   |  |
| <b>4.1 Desired/ suggested capacity</b>  |  |
| 4.1.1 Capacity of lyophilizer is standardized as 30 sq m shelf area or nearest standard size  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>4.2 Standard batch size</b>  |  |
| 4.2.1 Single load should contain 50000 vials of size 10R<br>4.2.2 600 L bulk volume   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>4.3 Change Over Time (if applicable)</b>   |  |
| Not applicable  |  |
| <b>4.4 Cleaning/sanitization/sterilization Time (if applicable)</b>   |  |
| 4.4.1 Vendor shall provide approximate period of cleaning (CIP) and sterilization (SIP). However total time for CIP and SIP of lyophilizer followed by cooling of the chamber to 25°C should not be more than 12 Hours.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>4.5 Other Productivity Requirement</b>   |  |
| 4.5.1 Vendor shall inform the total water consumption for CIP   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>5.0 Safety requirement</b>   |  |
| <b>5.1 General</b>  |  |
| 5.1.1 Following facilities must be provided to protect personnel, article and equipment:  |  |
| 5.1.1.1 In the event of equipment malfunction or loss of utilities, the unit must contain   | <input type="checkbox"/> Yes <input type="checkbox"/> no |



**PHARMA DEVILS**

PRODUCTION DEPARTMENT

**USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER**

| Specifications   | Compliance   |
|--|--|
| all necessary protection devices to ensure that the equipment and the article remain in a safe condition.  |  |
| 5.1.1.2 Noise level below 80 db at a distance of 1 m from the equipment  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.1.1.3 Emergency stop function on all accessible areas  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.1.1.4 For the safety of the operator the external surfaces should not have temperature more than 45°C.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.1.1.5 Warning stickers on all hot surfaces   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.1.1.6 Appropriate failure detection and alarm notification   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>5.2 Power failure and recovery</b>  |  |
| 5.2.1 A system has to be defined to guarantee the integrity of the system and the data in case of power failure.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.2.2 <b>In case of a power failure the product must be kept in a stable situation:</b> 1 vacuum pump and 1 cooling compressor must be running and hold temperature and vacuum (power supply of the vacuum pump and the cooling compressor via separate emergency power supply). The control section including all necessary devices like transmitter, PLC and visualization system have to be supplied via the existing UPS system on site. Vendor to specify UPS capacity requirement. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.2.3 In case of power failure the valve between the drying chamber and ice condenser should remain in previous position before power failure.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 5.2.4 A central vacuum valve between the condenser and the vacuum system must be provided. In case of power failure this valve has to close immediately and automatically.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>5.3 Containment</b>   |  |
| Not Applicable   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.0 GMP requirements</b>  |  |
| <b>6.1 Process control</b>   |  |
| The lyophilization system should essentially have the necessary provision for the control of following process critical parameters   |  |
| 6.1.1 Shelf temperature within +/- 1°C   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.2 Condenser temperature  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.3 Chamber temperature  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.4 Product temperature (on each shelf)  | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications |  | Compliance   |
|----------------|--|--|
| 6.1.5          | Rate of cooling ( minimum -1 °C /minute)   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.6          | Rate of heating (minimum 1°C /minute for empty chamber)  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.7          | Chamber pressure/vacuum (maximum vacuum upto 10 microbar with empty chamber)   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.8          | Compressed air line pressure for pneumatic control   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.9          | Differential pressure across the vacuum break filter   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.10         | Cleaning process parameters  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.1.11         | Sterilization process parameters (temperature, pressure and time)  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.2</b>     | <b>Failure mode detection</b>  |  |
|                | The equipment should generate audio-visual alarm and print the alarms in case of following failure.  |  |
| 6.2.1          | Process critical parameter exceed defined limit  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.2.2          | Failure of critical equipment component which can affect the product quality directly or indirectly  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.2.3          | Process critical instrument loop disconnected  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.2.4          | Failure in utility supply  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.2.5          | Failure in data communication  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.2.6          | GMP critical test failure i.e. chamber integrity test failure, pressure rise test.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.2.7          | <b>Vendor shall propose detail list of alarm in functional specification. The alarm list shall be finalized with the final user during discussion detail engineering design of the equipment</b> | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.3</b>     | <b>In –Process control</b>   |  |
|                | Not Applicable   | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications   |  |                       |                     |                           |       |         |           | Compliance   |
|--|--|-----------------------|---------------------|---------------------------|-------|---------|-----------|--|
| <b>6.4 Level of instrumentation</b>  |  |                       |                     |                           |       |         |           |  |
| Sufficient and suitable instrumentation for the process, safety and productivity controls as indicated in the following table: |  |                       |                     |                           |       |         |           |  |
| Type of control  | Purpose  | Operation range       | Desired Least Count | Extent of Instrumentation |       |         |           |  |
|  |  |                       |                     | Indication                | Alarm | Control | Recording |  |
| Temperature  | For controlling/ monitoring the shelf temperature                    | (- 80)°C to (+ 150°C) | 0.1°C               | Y                         | Y     | Y       | Y         | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Temperature  | For controlling/ monitoring the condenser temperature                | (- 80)°C to (+ 150°C) | 0.1°C               | Y                         | Y     | Y       | Y         | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Temperature  | For controlling/ monitoring the chamber temperature                  | (- 80)°C to (+ 150°C) | 0.1°C               | Y                         | Y     | Y       | Y         | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Temperature  | For controlling/ monitoring the product temperature                  | (- 80)°C to (+ 150°C) | 0.1°C               | Y                         | Y     | Y       | Y         | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Temperature  | For controlling/ monitoring the Chamber drain temperature during SIP | (- 80)°C to (+ 150°C) | 0.1°C               | Y                         | Y     | Y       | Y         | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|  |  |                       |                     |                           |       |         |           | <input type="checkbox"/> Yes <input type="checkbox"/> no |





# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications |   |                        |        |   |   |   |   |  | Compliance   |
|----------------|---|------------------------|--------|---|---|---|---|--|--|
| Temperature    | For controlling/ monitoring the condenser drain temperature during SIP  | (- 80)°C to (+ 150°C)  | 0.1°C  | Y | Y | Y | Y |  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Temperature    | For controlling/ monitoring the sterile filter drain temperature during SIP                                   | (- 80)°C to (+ 150°C)  | 0.1°C  | Y | Y | Y | Y |  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Temperature    | For controlling/ monitoring the coolant temperature in shelf heat exchanger and condenser at inlet and outlet | (- 80)°C to (+ 150°C)  | 0.1°C  | Y | Y | Y | Y |  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Pressure       | For controlling/ monitoring the lyophilizer chamber pressure  | Full vacuum to 3.0 bar | 1 mbar | Y | Y | Y | Y |  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| Pressure       | For controlling/ monitoring the lyophilizer condenser pressure  | Full vacuum to 3.0 bar | 1 mbar | Y | Y | Y | Y |  | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications |  |                        |         |   |   |   |   | Compliance |
|----------------|--|------------------------|---------|---|---|---|---|------------|
| Pressure       | For monitoring/controlling the pressure across the sterilizing grade vacuum break filter | Full vacuum to 8.0 bar | 0.01bar | Y | Y | Y | Y |            |
| Pressure       | For monitoring the main compressed air line pressure for pneumatic control               | 0 to 8.0 bar           | 0.1 bar | Y | Y | Y | N |            |

**Y Required, N Not required**

### 6.5 Cleaning requirement

|       |  |  |
|-------|--|--|
| 6.5.1 | The lyophilizer shall be cleaned by dedicated CIP system. Vendor shall provide detail CIP arrangement and process with requirement of space, load, technical detail and control system in the technical offer                          | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.5.2 | The lyophilizer shall be sterilized by dedicated SIP system. Vendor shall provide detail CIP arrangement and process with technical detail and control system in the technical offer. Pure steam supply shall be provided by the user. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.5.3 | Recommended cleaning agents are mild alkaline solution, purified water/ WFI  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.5.4 | Design of equipment should enhance cleaning feasibility by providing minimum sharp corners, minimum crevices & smooth finished welds joints.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.5.5 | Parts, which are required for cleaning, should be provided with quick fixing arrangement.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.5.6 | All gaskets provided to avoid leakage should be amenable for easy removed & re-fixing.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.5.7 | All bolts, nuts on the exterior part of equipment will be with cap head or cap nut.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |

### 6.6 Qualification requirement

|       |   |  |
|-------|---|--|
| 6.6.1 | All equipments shall be qualified with life cycle approach, i.e. DQ, IQ, OQ & | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|-------|---|--|



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications   | Compliance   |
|--|--|
| PQ. Vendor shall provide all documentation support including protocol subject to approval by the user.   |  |
| 6.6.2 Vendor shall provide execution support to the user to complete all stages of the qualification report.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.6.3 Steaming in place sterilization process shall be validated by empty chamber heat distribution and bio-challenge study to ensure the temperature uniformity within the chamber at $122 \pm 1^\circ\text{C}$ during hold time and reduction of bioload by more than 6 log when challenged by <i>B. stearothermophilus</i> spore strips containing $10^6$ spores per strips.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.6.4 Sterility assurance shall be verified by three consecutive and successful process simulation (media fill) trial  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.7 Material of construction</b>  |  |
| 6.7.1 All following metallic critical contact surfaces should be constructed of 316L grade stainless steel or better with internal mirror surface finish $< 0.5 \mu\text{m Ra}$ and external surface finish $< 1.2 \mu\text{m Ra}$ , matte finish.<br>a) Surfaces coming in direct contact of product<br>b) Surface coming in contact of washing and sterilization media i.e. WFI, purified water, pure steam<br>c) Surface coming in contact of sterile gas | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.7.2 All non product contact metallic surfaces should be constructed of 304 grade stainless steel or better (316 steel for sterile area equipment), external surface finish $< 1.2 \mu\text{m Ra}$ , matte finish.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.7.3 Gaskets, seals and O-rings coming in direct / indirect contact surfaces should be constructed of USFDA approved polymeric materials only.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.7.4 All welds should be ground finished to $< 1.2 \mu\text{m Ra}$ and properly passivated.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.7.5 Clean media pipes should be orbital welded   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.7.6 Insulation material should be non-fibrous and covered with completely welded SS 304 or better cladding.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.8 Use of lubricants</b>   |  |
| 6.8.1 Any lubricant, if used in the equipment must be food grade and non-toxic. Used lubricants must not come in contact of the potential product contact surfaces.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.8.2 Vendor shall give detail on the coolant and drying media used in the system.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

|             |   |  |
|-------------|---|--|
| <b>6.9</b>  | <b>21 CFR Part 11 compliance</b>  |  |
|             | A criticality assessment is to be made to assess the applicability of the system to Part 11 regulation. Software, if used to generate, process, store the quality critical data must be validated and must comply 21 CFR Part 11 requirements | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.10</b> | <b>Data integrity</b>   |  |
|             | System security access shall consist of the following profiles-:  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|             | a) Operator: Shall provide operator access to allow routine operation of all equipment features   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|             | b) Supervisor: Shall provide access to operator level features in addition to critical operating parameter configuration  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|             | c) System administrator: Shall provide the access to the Operator and Supervisor level features in addition to system security parameters.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.11</b> | <b>Batch record printing</b>  |  |
|             | A complete batch record indicating the following important parameters, but not limited to these:  |  |
| 6.11.1      | Equipment identification number   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.2      | Process code &/or identification (process program number)   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.3      | Program information and parameters  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.4      | Start date and time   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.5      | End date and time   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.6      | All failures and alarms.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.7      | Process record, preferably a real time graphical representation for important process controls parameters.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.8      | Operator code and name  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.9      | Adequate space for writing remarks / corrective actions if any.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.10     | Identified space to sign for operator & supervisor.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.11.11     | There should be a possibility to store and archive the data for future retrieval and analysis.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications  | Compliance   |
|---|--|
| <b>6.12 Desired documents</b>   |  |
| 6.12.1 Following documents, but not limited to these, are expected from the vendor as part of the supply package as hard copy and electronic editable version in English language                           | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1 Functional design specification containing:  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.1 Equipment descriptions   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.2 Equipment operation steps  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.3 HMI functions with screen shot   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.4 List of failure indications  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.5 List of interlocks and block diagram with their functions and Alarms.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.6 Critical list of major component, devices and instruments with their specific functions, specification data sheet.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.1.7 Schematic diagram of the equipment   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.2 Operation and maintenance manuals, preventive maintenance schedule for equipment major component as well as the operating system   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.3 Operation and maintenance manuals for the bought out items.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.4 Installation instructions/ guideline for equipment   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.5 Final As-built drawing for equipment   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.6 Detailed drawing (Plan and minimum one elevation) marking clearly all the necessary dimensions and locations of utilities along with requirement of utilities on the drawing along with the offer. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.7 Other drawings (such as PID, electrical, instrumentation etc.)   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.8 Software ladder logic/ operation and controls flow charts  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.9 Spare and/ or change parts list with ordering information  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.10 MOC certificates for all direct/ indirect product contact surfaces.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.11 Instrument calibration certificates with respect to the traceable national reference standard instrument and their calibration procedure.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.12 Factory acceptance test specifications and reports with actual test results/ data for equipment   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.13 Recommended SOP's for operation, cleaning and maintenance of each equipment   | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications   | Compliance   |
|--|--|
| 6.12.1.14 Guaranty/ warranty certificates for each equipment and major bought-out items, such as PLC, printer, recorders, instrumentation etc.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.15 21 CFR part 11 compliance report/ certificates for the software(s). (if applicable)  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.16 Software installation CD/ floppy with 2 back-ups, wherever applicable.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.17 Software recovery procedures in case of computer system breakdown, forequipment control system   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.18 Shipping checklist.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.19 DQ, IQ and OQ protocols  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.20 Control System input / output verification data & report   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.12.1.21 Types of Lubricant and Lubrication instructions. Food grade certificate.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.13 Training</b>   |  |
| a) A special training for operators has to be included in the offer.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| b) A special training for technical staff has to be included in the offer  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>6.14 GMP requirement (others)</b>   |  |
| 6.14.1 A clear separation between clean and technical area must be realized.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.2 Required leakage rate for chamber/condenser should be less than 0.01 mbar/l/s   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.3 All utility pipes specifically pure steam/ water for injection/ condensate should have sufficient slope towards drain for complete emptying of the pipes                        | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.4 All drives, filters, pumps, valves (specially chamber drain) should have easy access  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.5 The chamber safety valve should be of aseptic type with a sanitary flange connection. If vacuum tightness of safety valve could not be assured, a rupturedisk can be a solution | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.6 For all clean media a sampling valve should be provided at supply and in drain  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.7 All drains must be equipped with an air-gap before connected to the drainsystem on site   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.8 All drains should be at the lowest point of the chamber / condenser for completedrainage.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.9 All valve in contact of the clean media should be of sanitary type and suitable   | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications                         |   | Compliance   |
|--|---|--|
|  | for aseptic use (e.g. deadleg free, diaphragm type with PTFE or EPDM diaphragm)                                     |  |
| 6.14.10                                | The validation ports should be provided for inserting temperature probe for temperature mapping                     | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.11                                | The chamber should have sufficient slope for complete drainage  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.12                                | The stoppering system of the lyophilizer should not create any particle or affect the sterility of the system       | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.13                                | The sterile filters must be testable for integrity. An online integrity system should be proposed as optional       | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.14                                | An appropriate seal must be used for connecting the panelling to the suspended ceiling, clean room walls and floor. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.15                                | The front panelling on both sides must be gas tight to the technical area of the freeze dryer.                      | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 6.14.16                                | Vendor to give code numbers for each component  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>7.0 Technical requirement</b>       |   |  |
| <b>7.1 Basic technical requirement</b> |   |  |
| 7.1.1                                  | The layout must be taken into account when determining the layouts of the units.                                    | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.1.2                                  | A proposal of a possible installation layout should be added to the documentation.                                  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.1.3                                  | The manufacture has to give the clear details on the total weight, dimensions and the capacity of the equipment.    | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.1.4                                  | The heat given off by the unit must be stated.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.1.5                                  | The construction of the complete system should be described in the documentation in detail.                         | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.1.6                                  | Vendor shall provide special tools for assembling, disassembling and maintenance                                    | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>7.2 Level of automation</b>         |   |  |
| 7.2.1                                  | The equipment should operate with minimum operator involvement.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.2.2                                  | The equipment should control automatically all critical parameter and detect failure mode automatically.            | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications  | Compliance   |
|---|--|
| 7.2.3 Critical process parameters and failure modes are listed in the preceding sections.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.2.4 Human - machine interface (PC) must be used to enter the process details (minimum 20 recipe), which should appear in the print out in English. Print out must provide results of all critical process parameter and failure alarms.                     | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>7.3 Specific requirements</b>  |  |
| 7.3.1 All main technical installations (i.e. condenser, refrigeration unit etc) of the lyophilizer should be on the basement. Exact dimensions must be given by the supplier. Vendor shall also make proposal of a possible installation layout               | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.2 A pressure test according to EU regulations is required for at least the chamber and condenser  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.3 The panelling of the equipment should reach the suspended ceiling. The cladding panel should be constructed to allow easy removal for inspection and maintenance  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.4 The vendor shall provide the detail nozzle schedule of the chamber and condenser in the documentation   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.5 It has to be assured that fallen vials cannot reach the condensers under all conditions. The used precaution should be described  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.6 The door operation should be mechanized or automatic with an automatic locking system   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.7 For loading and unloading slot door shall be provided and hinge type main door shall be used for maintenance  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.8 The slot door opening vertically should operate automatically. The bid must include a description of both opening/closing and locking mechanisms.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.9 The drive system for the slot door movement must be located within the technical area. Any movement of rods e.g. between the technical area and the clean room areas is not permitted. The separation between the areas should be described in the bid. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.10 The slot door must be designed for semi-automatic loading and unloading of the freeze dryer.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.11 An illuminated sight glass within class A/B is required to allow visual control of stoppering by the operator.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.12 All doors must be interlocked if the pressure in the chamber goes above atmospheric pressure.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |





# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications |  | Compliance   |
|----------------|--|--|
| 7.3.13         | If any door is incorrectly closed the CIP and the SIP processes cannot be started.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.14         | The sealing mechanism for all doors should be described in the offer – static sealing will be preferred.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.15         | If dynamic sealings (or combined solutions of static and dynamic sealings) are used it has to be assured that only sterile compressed air is used for sealing operation.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.16         | All door sealings must operate without any additional lubricant.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.17         | It has to be assured that during CIP/SIP no liquids remain between door, sealing and chamber.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.18         | The replacement of any door sealing must be possible without disassembling of any other parts or components.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.19         | A hydraulic pressure test of the shelves with at least 4 bar (abs) shall be performed and documented.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.20         | The operating temperature of the shelves should be between -55° to +70°C.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.21         | It has to be sure, that no vials will fall from the sides of the shelves. Therefore the shelves shall be executed with a border system on the sides to ensure coherent lyo conditions even on the shelf edges. If a different system will be used to ensure this, it has to be described in the documentation. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.22         | The shelf clearance should be suitable for all sizes of the vials with a system of changing the shelf clearance  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.23         | The collapsing (and levelling after CIP/SIP) of shelves should be performed automatically. The construction should be described in the documentation.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.24         | The shelves must be levelled and constructed to a tolerance of at least +/- 0.5mm/m or less.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.25         | A constant loading level (for the loading and unloading system) is required. Therefore a defined position (approx. 1000 mm above floor) must be reachable with each shelf during loading and unloading.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.26         | It must be possible to define the constant level infinitely variable via software for each shelf separately (no hardware based solution like limit switch permitted). A description of the used system shall be added to the bid (optional).   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.27         | The accuracy of the positioning system should be at least +/- 0.5 mm or better.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.28         | In addition the position of each shelf must be mechanically adjustable (to ensure minimum tolerances concerning constant loading level for each shelf).  | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications                                     |  | Compliance   |
|--|--|--|
| 7.3.29   | The bottom part of the shelves should be specially treated to avoid the sticking of stoppers (glass-pearl blasted e.g.).   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.30   | The connection of heating/cooling media to the shelves should be completely welded; flanging is not permitted.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.31   | Even under vacuum conditions no silicon oil (gas) is permitted to be detectable within the chamber.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.32   | The tightness of the tubes and the whole system must be checked via He-leak-test (and documented) before and after installation within the chamber.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.33   | All the shelves shall be pressure tested at 20% higher than the design pressure. X-ray test: One sample shall be X-ray tested only for checking. In case of failure 100% shelves shall be X-ray tested.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| 7.3.34   | The vendor shall provide detail information of all critical technical components which are Aeration system, Ice condenser, vacuum generation system, primary cooling system, heating/cooling system for shelves  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>8.0 Good Engineering Practices Requirements</b> |  |  |
|  | a) Equipment must be fabricated following all Good Engineering Practices. The vendor's Quality System must follow applicable national or international standards.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|  | b) Vendor must generate all applicable documents during all phases of equipment fabrication i.e. design, fabrication, testing and shipment as per applicable standards e.g. GAMP.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|  | c) All sensors, controllers, PLC, transmitters, indicators and any other controller or indicators to read, print or control any of the parameter, will have to be calibrated, traceable to National or international standards. Original calibration certificate along with traceability to be submitted by vendor in their IQ file. | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|  | d) All material of construction should have test certificate   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
|  | e) Vendor must generate and provide all specifications and test certificates of software used in the equipment control and/or monitoring system.   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>8.1 Inspection and testing</b>                  |  |  |
|  | ➤ System shall be inspected and tested (FAT) at the supplier's site in the presence of user's representative before delivery.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

| Specifications  | Compliance   |
|---|--|
| <b>9.0 Constraints</b>  |  |
| <b>9.0 Equipment location and available space</b>   |  |
| This equipment will be installed in the <u>Sterile bulk and formulations Facility</u> . The equipment location is indicated in the relevant block of the layout enclosed  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>9.1 Available utility</b>  |  |
| <ul style="list-style-type: none"><li>➤ Electricity: _____(Report Requirement)</li><li>➤ Purified Water _____(Report Requirement)</li><li>➤ Water for injection _____(Report Requirement)</li><li>➤ Pure steam _____(Report Requirement)</li><li>➤ Compressed air / nitrogen pressure _____(Report Requirement)Note:<br/>Vacuum system to be supplied by the Vendor</li></ul> | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| <b>9.2 Timelines</b>  |  |
| a) Response to URS: Within 2 weeks of receipt of URS  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| b) Quotation Submission: Within four weeks of receipt of URS  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| c) Submission of detail functional design specification, Design Qualification(DQ) and schematic drawings: Four weeks after order finalization   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| d) Submission of FAT/SAT Specification-: Four weeks after order finalization  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| e) Submission of Installation Qualification (IQ) and Operational Qualification(OQ) protocols: Two months after order finalization   | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| f) Mechanical and electrical drawings: Two weeks before FAT.  | <input type="checkbox"/> Yes <input type="checkbox"/> no |
| g) Submission of control system details and control system verification protocol: 2 weeks before FAT  | <input type="checkbox"/> Yes <input type="checkbox"/> no |



# PHARMA DEVILS

PRODUCTION DEPARTMENT

## USER REQUIREMENT SPECIFICATION FOR LYOPHILIZER

### 10.0 Abbreviation:

| Terms  | Abbreviation                               |
|--------|--|
| CD     | Compact Disc                               |
| CFR    | Code of Federal Regulation                 |
| DQ     | Design Qualification                       |
| EU-GMP | European –Good Manufacturing Practice      |
| FAT    | Factory Acceptance Test                    |
| GAMP   | Good Automated Manufacturing Practices     |
| GMP    | Good Manufacturing Practices               |
| HMI    | Human Machine Interface                    |
| IQ     | Installation Qualification                 |
| ISO    | International Standards Organization       |
| MOC    | Material Of Construction                   |
| OQ     | Operational Qualification                  |
| Ph     | Phase                                      |
| PID    | Proportional Integral Derivative.          |
| PLC    | Programmable Logic Controller              |
| PQ     | Performance Qualification                  |
| RTD    | Resistance Temperature Device              |
| RTP    | Rapid Transfer Port                        |
| SAT    | Site Acceptance Test                       |
| SOP    | Standard Operating Procedures              |
| SS     | Stainless steel                            |
| TGA    | Theraupeatic Goods Authority               |
| UPS    | Uninterrupted Power Supply                 |
| US FDA | United State Food and Drugs Administration |
| WFI    | Water For Injection                        |
| WHO    | World Health Organisation                  |