URS No.:



# USER REQUIREMENT SPECIFICATION FOR AOUTOCLAVE CUM BUNG PROCESSOR

LOCATION:	AMPOULE LINE
SUPERSEDES URS No.	NIL



URS No.:

# URS CONTENTS TITLE

S.No.	TITLE	PAGE No.
1.0	APPROVAL	03
2.0	OBJECTIVE	04
3.0	SCOPE	04
4.0	RESPONSIBILITY	05
5.0	GMP / REGULATORY REQUIREMENTS	06
6.0	SYSTEM OVERVIEW	07
6.1	TECHNICAL SPECIFICATION	08
7.0	OTHER REQUIREMENT AND CONSTRAINTS	11
8.0	LIFE CYCLE	12
8.1	DEVELOPMENT	12
8.2	TESTING	12
8.3	SUPPORT	12
8.4	DELIVERY	12
9.0	DOCUMENTS TO BE ATTACHED	12
10.0	REVIEW COMMENTS	13
11.0	ABBREVIATIONS	14



# **1.0 APPROVAL:**

# **INITIATED BY:**

DESIGNATION	NAME	SIGNATURE	DATE
OFFICER/EXECUTIVE (QUALITY ASSURANCE)			

### **REVIEWED BY:**

DESIGNATION	NAME	SIGNATURE	DATE
HEAD (PRODUCTION)			
HEAD (ENGINEERING)			

### **APPROVED BY:**

DESIGNATION	NAME	SIGNATURE	DATE
HEAD (QUALITY ASSURANCE)			



### 2.0 **OBJECTIVE:**

- The User Requirements Specification (URS) is provided to aid the user through the critical aspects of Fabrication, Facility for Installation of Required Equipments, Cleaning / Proper Maintenance, cGMP, Safety and Regulatory Requirements necessary to construct and fabricate a functional Steam Sterilizer that meets the user's needs in the most cost-effective method possible.
- The URS to be provided to Vendor to submit a Price Quote for procurement of Steam Sterilizer..
- The URS shall help Vendor in understanding the end user requirement in details. This document shall help vendor for developing the Design Specification, which on approval by site will become a Contractual Agreement between vendor and the Site.
- This URS shall be recognized as an integral part of the procurement agreement with the vendor. The vendor will abide by the information and conditions set forth by this document as well as the Standard Purchase Terms and Conditions of the Site.

# **3.0 SCOPE:**

- The Scope of this document is limited to the User Requirement Specification (URS) of Autoclave cum bung processor of the Site.
- The URS shall be used as a reference document for Design Qualification considering all aspects of Current Good Manufacturing Practices (cGMP) and safety.





### 4.0 **RESPONSIBILITY:**

The validation group, comprising of a representative from each of the following departments shall be responsible for the overall compliance of this URS:

DEPARTMENTS	RESPONSIBILITIES		
	• Preparation, Review, and Approval of User Requirement		
	Specification.		
Quality Assurance	• Co-ordination with Production, Engineering and Quality Control to		
	prepare User Requirement Specification.		
	• To check the completeness and Technical Accuracy of the URS.		
Production	• Review of User Requirement Specification for compliance with the		
Troduction	Process Requirement.		
Engineering	• Review of User Requirement Specification.		
	• Assist in preparation of User Requirement Specification.		



# 5.0 GMP / REGULATORY REQUIREMENTS:

The purpose of Steam Sterilizer is sterilization for Machine Parts & Clean Room Garments.

- Autoclave cum bung processor shall comply to the "Current Good Manufacturing Practices".
- WHO GMP "Good Manufacturing Practices for Pharmaceutical Products".
- ► HTM 2010.
- Schedule –M–"Good Manufacturing Practices and Requirements of Premises, Plant and Equipment for Pharmaceutical Products."



# 6.0 SYSTEM OVERVIEW:

- Autoclave cum bung processor shall be able to sterilize the Machine parts, Accessory & Clean Room Garments with following cycles:
- Vacuum Leak test
- Bowie Dick test
- Standard Process for non porous load
- High Pressure High Vacuum cycle for Porous load
- Siliconization cycle
- Fluidilization cycle
- Autoclave cum bung processor shall be equipped with following component:

# **Door & Door Components**

• Double Door system

 $\triangleright$ 

- Pneumatic Door Operating Cylinder: To Open/Close the Doors.
- Solenoid Valves for Door Operating Cylinder: To operate the door cylinders.
- Pressure Switch: To set the pressure level for the Gasket.
- Pressure Gauges: one on non sterile door side for jacket pressure.
- Vacuum Switch: To set the vacuum level for the Gasket.
- Compound Gauges: Indication of Gasket Pressure.
- FRL: To filter regulate & lubricate the incoming compressed air.
- Regulator: To regulate the incoming compressed air.
- Ejector: To retract the gasket for opening the door.
- Limit Switch: Limit switches to signal the door close position.

# > Water Recirculatory System:

- Solenoid Valve for Pneumatically Actuated Ball Valve: To operate the rotary actuated ball valves.
- Steam Trap: To prevent steam loss along the condensate removal line.

# Process Control:

- Safety Valve : Chamber over pressure protection
- Non return valve : To prevent back pressure in compressed air line
- Compound gauge: Chamber pressure
- Pt-100 Temperature Sensors for temperature monitoring in the chamber
- Vacuum Switch: For air inlet in case of emergency vacuum.



URS No.:

# 6.1 TECHNICAL SPECIFICATION:

S.No.	SYSTEM DESCRIPTION	МОС	TECHNICAL SPECIFICATION	
1.0	Chamber			
	Туре		Rectangular	
	Chamber internal size		900 (W) X 900 (H) X 1200 (D) mm	
	Chamber Volume		972 Liters	
	МОС	SS 316L	As per CGMP Requirement	
2.0	Jacket	Jacket		
	Туре		Rectangular	
	МОС	SS 304	As per CGMP Requirement	
	Туре		Rectangular	
3.0	Doors			
	Туре		Double Door, Vertical sliding	
	МОС	SS 316	As per CGMP Requirement	
	No of doors		02Nos.	
	Door insulation		Resin Bonded Glass wool	
4.0	Door gasket			
	МОС	Food Grade Silicon	As per CGMP Requirement	
	Size		As per equipment requirement	
	Working temperature		121-134 °C	
5.0	Door operating cylinder			
	Type of operation		Pneumatic	
	Mounting		Vertical	
	Door locking cylinder		Horizontal (2 nos.)	
6.0	Insulation			
	Insulation material	SS 316 L	As per CGMP Requirement	
	Outer cover	SS 304 L	As per CGMP Requirement	
7.0	Operating Parameter			
	Temperature		121-134 <sup>°</sup> C	



Pressure

Vacuum

Range

MOC

NO.

MOC

NO.

**Compound Gauge** 

S.No.

8.0

9.0

### **USER REQUIREMENT SPECIFICATION** FOR **AUTOCLAVE CUM BUNG PROCESSOR**

MOC

\_\_\_\_\_

-----

\_\_\_\_\_

SS316

URS No.:

**TECHNICAL SPECIFICATION** 

Approx 1.2-2.1 kg/cm<sup>2</sup>

Range - 1 to 6 To 6 kg/cm2 (g)

SS316L for Contact Part

As per CGMP Requirement

Full

\_\_\_\_\_ SS304 for Non Contact Part 02 \_\_\_\_\_ **Validation Port** SS316 As per CGMP Requirement 2 Nos. -----NO of sensor arrangement No of sensor arrangement in each port : 8

10.0 **Port for RTD Sensor** MOC

SYSTEM DESCRIPTION

	NO.		1 No
	NO of sensor arrangement		No of sensor arrangement in each port : 8
11.0	Switches		
	Pressure switch		02 Nos.
	Vacuum switch		02 Nos.
	Photo cell sensor		2 No. for door obstruction safety
12.0	Control Panel On Loading Side		
	Push button		Color push button for – Loading door open & close Emergency stop
	Indication lamp		Door pre condition
			Alarm indication
	Strip chart recorder		Strip chart recorder on loading side
	MMI		Onto the control panel
13.0	Control Panel On Unloading	Side	
	Push button		Color push button for – • Loading door open & close • Emergency stop • Door open acknowledge



URS No.:

#### S.No. SYSTEM DESCRIPTION MOC **TECHNICAL SPECIFICATION** Door pre condition Indication lamp \_\_\_\_\_ Process on/end condition 14.0 Safety Both the door should not opened Door inter lock simultaneously Door shall be obstructed by hand Door obstruction \_\_\_\_\_ Make - radix Accuracy - Class A Temperature sensor 15.0 Pt 100 (Inside the chamber) Qty-04 Nos. Range – Approx 16.0 Air filter 0.2 micron -----Range – 0 to 200 $^{\circ}$ C Temperature indicator Make – Radix 17.0 \_\_\_\_\_ controller Qty -01 No. 18.0 Extension card As per your specification \_\_\_\_\_ 19.0 Printer Dot matrix Online printer \_\_\_\_\_ 20.0 Accessories Trolley SS 304 As per your design SS 316 With perforated shelves Carriage



# 7.0 OTHER REQUIREMENTS AND CONSTRAINTS:

# **7.1 LAY OUT:**

- Should accommodate Size of equipments, utility services to be provided, Operating space and clearance for maintenance activity.
- Should be suitable such that after placement of equipments in the area the scope for personal movement and maintenance activity is not disturbed.

# 7.2 FUNCTIONAL REQUIREMENTS:

• The system shall comply with cGMP. Autoclave cum bung processor shall comply with the "Current Good Manufacturing Practices".

# 7.3 UTILITY REQUIREMENTS:

- System shall accept Three Phase  $415 \pm 10\%$  V supplies.
- Pure Steam Gas Inlet

# 7.4 SAFETY REQUIREMENTS:

- Emergency push button shall be provided.
- Electric panels shall not have any unsecured joints.
- Double earthing shall be provided for all electrically operated equipments.
- Noise pollution shall be kept below 80 db.
- Safety valves to Protect chamber & Jacket from over pressure.
- Insulation to Jacket to prevent opening of Door under pressure.
- Pressure Switches to protect chamber & Jacket from over pressure.

### 7.5 MAINTENANCE:

- The Equipment shall allow for maintenance by trained site personnel with supplier recommended tools and practices.
- Recommended spare parts list shall be provided.
- The supplier shall provide all spare parts at the production site before the start of Steam Sterilizer.
- The supplier shall replace the parts found to be damaged/ broken during installation.
- The supplier shall be available at the site when asked in case of major breakdown.



### 8.0 LIFE CYCLE

### 8.1 **DEVELOPMENT:**

• The supplier shall follow cGMP practices in design, development, construction and Installation of the system.

### 8.2 TESTING:

- The system shall be Factory tested by the supplier with approval witness.
- The system shall be commissioned and qualified at site for Installation and Operation by the supplier with approval witness.

# 8.3 SUPPORT

• Supplier shall provide support for Preventive maintenance plan development, Operator training, Cleaning of the equipment etc.

### 8.4 **DELIVERY**

- All parts of the system shall be sourced, delivered and installed by the Supplier.
- The supplier shall provide Functional design specification and other qualification documents (DQ, IQ & OQ) in soft copy.

# 9.0 DOCUMENTS TO BE ATTACHED:

- All MOC Certificates, Manual for Bought out items
- Design Qualification protocol.
- Installation Qualification protocol.
- Operational Qualification protocol.
- Schematic Diagram of machine showing Overall Dimensions.
- Instrument list with manufacturer's calibration certificate.
- Electrical unit Diagram.
- P&ID Diagram / G.A Drawing.
- Operating & Service Manual
- Spare Part List.
- Warranty Certificate of machine
- Test Certificate of SS Materials



### **10.0 REVIEW / COMMENTS:**

- The supplier should make/design the Autoclave cum bung processor as per technical specification mentioned in the URS.
- For any changes in the design/make of the HPHV, if not as per the URS, prior intimation/approval should be taken by the supplier from the site.
- All parts should have MOC certificates, test certificates, Calibration certificates for traceability and authenticity.

Reviewed By Manager Engineering Sign / Date



# **11.0 ABBREVIATIONS:**

URS	:	User Requirement Specification
cGMP	:	Current Good Manufacturing Practices
ISPE	:	International Society of Pharmaceutical Engineering
cGEP	:	Current Good Engineering Practices
DQ	:	Design Qualification
IQ	:	Installation Qualification
OQ	:	Operational Qualification
MOC	:	Material of Construction
SS	:	Stainless Steel
WHO	:	World Health Organization